AMERICAN INTERNATIONAL UNIVERSITY-BANGLADESH

FACULTY OF BUSINESS ADMINISTRATION
DEPARTMENT OF MANAGEMENT

PROJECT MANAGEMENT
GROUP ASSIGNMENT
PROGRAM:
SECTION:

SL : **ID :**	**GROUP:**
Name:	**Signature:**

PROJECT TITLE :

SL	DOCUMENT / TOPIC	CHECKED	DATE
1	Sample of Resource Allocation & Cost Estimation		/ /
2	RESOURCE LIST		/ /
3	COST ESTIMATE		/ /
4	SAMPLE OF EARNED VALUE ANALYSIS		/ /
5	EARNED VALUE MANAGEMENT		/ /
6	MILESTONE REPORT		/ /
7	PROGRESS REPORT		/ /

GROUP:

PROJECT TITLE :

GROUP MEMBERS

SL	ID	Name

1. Sample of Resource Allocation & Cost Estimation

Resource requirement of the activities of a project is summarized below

Activity	Predecessor (s)	Duration (hr)	Planned Resources
A		4	3 W, 2 ME, 1 Archit.,1 OP & 1 COMP
B		5	10 W, 1 ME, 1 Excavator, 10 truck Earth
C	B	6	4 W, 3 ME, 2 COMP, 2 OP
D	A	4	5 W, 1 ME, 100 m CIS, 500 m iron wire
E	C	2	4 W, 1 ME, 50 pole, 200 m Bar, 50 m CIS
F	C	4	4 W, 2 ME, 2000 Br, 50 bags Cem., 50 cft Sand
G	D	5	2 W, 1 ME, 180 cft Aggregate, 5 ton Rod, 30 bags Cem
H	D	3	6 W, 2 ME, 5000 Br, 250 bags Cem., 150 cft Sand
I	F, G	8	3 W, 2 ME, 8000 Br, 400 bags Cem., 250 cft Sand, 50 ton Rod, 150 cft Aggregate
J	E	4	4 W, 1 ME, 2 Elc., 2 PF, 500 m wire, 400 m pipe
K	H	2	8 W, 50 bags Cem

Note: 6 working days in a week, 4 weeks in a month, and 8 hours working time in a day

W = Worker
OP = Operator
Cem = Cement
m = meter
Br = Brick
PF = Pipe Fitter
ME = Management Employee
Archit = Architect
COMP = Computer
Elc. = Electrician
CIS = Corrugated Iron Sheet

Price, Rent, and Salaries & Wages:

W = $1.5/hr
ME = $1100/Month
Archit = $2000
OP = $2/hr
COMP = $3/hr
Excavator = $10/hr
Elc. = $3/hr
PF = $3/hr
Earth = $125/truck
CIS = $1.5/m
Iron Wire = $.3/m
Pole = $75/ piece
Bar = $3/m
Br = $0.1/piece
Cem. = $5/bag
Sand = $0.2/cft
Aggregate = $2/cft
Rod = $800/ton
Wire = $0.4/m
Pipe = $0.5/m

1. (a) Calculate the cost of the activities, and that of the project.
   (b) Draw the Gantt chart of the project
   (c) Calculate the amount required for the first 10 hrs and the last 10 hrs..

2. RESOURCE LIST	
Project Title:	

WBS CODE	RESOURCE TYPE	RESOURCE NAME	QUANTITY

3. COST ESTIMATE	
Project Title:	

SL	WBS COST ELEMENT	TOTAL COST	TOTAL PERCENTAGE
1.	INITIATING		~2%
2	PLAANING		~15%
3	EXECUTING		~75%
3.1			
3.2			
3.3			
3.4			
3.5			
3.6			
3.7			
3.8			
3.9			
4	MONITORING & CONTROLLING		~5%
5	CLOSING		~3%

4.A Sample of EARNED VALUE ANALYSIS

The following project is at the end of its 5 week.Find the cost and schedule variances. Also find the CPI, SPI, CSI, ETC and EAC for the project.

Activity	Predecessor (s)	Duration (week)	Budget ($)	Actual Cost ($)	% Complete
A		4	300	400	100
B		5	200	180	40
C	A	6	250	300	50
D	A,B	4	600	400	100
E	A,B	2	400	200	100
F	C	4	150	180	60
G	D,F	5	100	200	75
H	E,G	3	500	350	25

5.EARNED VALUE MANAGEMENT	
Project Title:	

6. MILESTONE REPORT	
Project Title:	

MSL	Milestone List	Target / Finish Week	Status (%) Completed	Issues / Comments
M01				
M02				
M03				
M04				
M05				
M06				
M07				
M08				
M09				
M10				
M11				
M12				
M13				
M14				

7. PROGRESS REPORT	
Project Title:	
Report Period	

Work completed this reporting period:
Work to complete next reporting period:
What's going well and why:
What's not going well and why:
Issues/Suggestions/Changes: